

LOWER WAIRARAPA VALLEY DEVELOPMENT SCHEME

OCTOBER 2000 FLOOD DAMAGE SCHEDULE

Site	Damage	Repair Work	Cost (\$)	Priority
Ruamahanga - Tobin	Bank slump	Boulder rip rap	12,000	High
Ruamahanga - Herrick	Rip rap damaged	Rock armouring	20,000	High
Ruamahanga - Butcher	New slump	Rejects	8,000	High
Ruamahanga – Leo Vollebreght	Two bank slumps	Two boulder rip raps	12,000	High
Ruamahanga – Smith- Waihenga	Rip rap damaged	Rock armouring	15,000	Medium
Ruamahanga - McCloed Est	Rip rap damaged	Rock armouring	12,000	High
Ruamahanga – Shelton	Bank erosion	Two willow clumps	6,000	Medium
Tauherenikau – Gillett mail box	Stopbank overtop & damage	Repair & strengthen stopbank	15,000	High
Tauherenikau – Gillett Stopbank	Stopbank breach (new breach)	Repair stopbank	20,000	High
Tauherenikau – Gillett Stopbank	Stopbank breach (widening the old breach)	Repair stopbank	20,000	High
Wairongamai - Matthews	Bank erosion & risk of course change	3 retards	12,000	Medium
TOTAL			\$ 152,000	