

UpperRuamahanga  
Flood Damage ScheduleMt Bruce Scheme  
February 2004

<b>Site</b>	<b>Damage</b>	<b>Repair</b>	<b>Cost(\$)</b>	<b>Priority</b>	
Ravenstone	Bank erosion 180m	Channel alignment/shingle groynes Planting	12000 2000	M M	
Edwards	Bank erosion 25m	*Willow cabling	2000	M	H - High
Van Barnveld	Bank erosion 120m	*Willow clumps	6000	M	M - Medium
		Channel alignment	3000	H	
Graham Stuart	Bank erosion 150m with threat of river course change	Major channel realignment	15000	H	
		Willow clumps	7000	H	
		*Widening of the narrow section	25000	H	
Duncan Stuart	Bank erosion 100m with threat of river course change	Channel realignment	16000	H	
		Willow clumps	8000	M	
Duncan Stuart	Bank erosion 40m	*Willow cabling	2000	M	
McLachlan	Bank erosion	Channel alignment	6000	M	
		*Rail groynes/Willow clumps	7000	M	
Te Ore Ore "Crusher"	Bank erosion	*Willow clumps	7000	M	
		<b>Total</b>	<b>118000</b>		
		Amount to be accommodated in the current years programme	<b>16000</b>		
		*Items programmed for the next financial year	<b>49000</b>		
		<b>Net amount</b>	<b>53,000</b>		